



LIMESTONE FIRE PROTECTION DISTRICT

5262 East Hwy 20, Claremore, OK 74019 918-341-6430 FAX 918-343-2302

www.limestonefd.org

July 9, 2017

To: Interested Contractor

From: Limestone Fire Protection District

RE: Request for Quote – New Sidewalk for Station 1

Bid # 2017-06

Limestone Fire Protection District is seeking a written quote from a qualified, licensed, and insured contractor to pour a new sidewalk along the west side of station and north side of training room covered porch at the following locations:

Station 1: 5262 E Hwy 20, Claremore, OK 74019

A quote on contractor/vendor letterhead must be received electronically (email or fax) or U.S. Mail by Friday, August 4, 2017, 5:00 pm. Any quote received after the required time and date specified for receipt shall be considered late and non-responsive. Any late quotes will not be evaluated for award. If submitted electronically, e-mail to info@limestonefd.org or Fax 918 343-2302 with the subject line to read Request for Quote – Station 3 Driveway. Mailing Address: 5262 E Hwy 20, Claremore, OK 74019 Attn: Edward Bell

Further information may be obtained by calling the District Office at (918) 341-6430 or email at info@limestonefd.org.

The bid will be awarded at Limestone Fire Protection District regular business meeting on Sunday, August 13th at 3:00 pm.

LFPD reserves the right to reject any or all proposals, to waive any defects in the proposals received, and to select the consultant considered the most advantageous to the District.

Sincerely

Edward Bell

cc: Clerk

REQUEST FOR QUOTE (RFQ)

I. PURPOSE:

The District is seeking a qualified, licensed and insured contractor to pour a new sidewalk along the west side of building at Station 1 and north side of training room covered porch, as identified in the Scope of Work. The remainder of this document provides additional information that will allow a bidder to understand the scope of effort and develop a quote.

II. SCOPE OF WORK

A. Excavate:

- a. Grade and compact area for proper drainage. Build up areas as needed using materials that comply with the requirements of Sections 610.04 and 402.04 of the Standard Specifications for Highway Construction, Oklahoma Department of Transportation, 2009 Edition,

B. Concrete Work

- a. The project area is located on the west side of Station 1 and is defined as that portion starting from the 7'-0" from the northwest corner of the station, south to the training building, then turning along the north covered porch; Ending at where the existing side walk on the west side of the covered porch.
- b. The construction methods used to execute the work will comply with the requirements of Sections 610.04 and 402.04 of the Standard Specifications for Highway Construction, Oklahoma Department of Transportation, 2009 Edition,
- c. Supply and forms to Grade. Supply, pour and finish 4" of ODOT Class A 3500 psi. by 36" wide concrete with ODOT approved rock and Fibermesh. Saw cut with a Soffcut saw per ACI standards and apply an ODOT approved cure and seal.

C. Clean up site

III. SERVICE, SERVICE AND ANNUAL MAINTENANCE

- A. Bidders will include warranty information on all repairs and services, including the length of the warranty.

IV. BIDDER RESPONSIBILITY

- A. The bidder is responsible for supplying their own tools, equipment, materials, and supplies.
- B. The bidder is responsible for supplying a current Certificate of Workers' Compensation prior to work commencing.
- C. The bidder is responsible for supplying Plans to the District and to Rogers County for purpose of obtaining all required permits.
- D. The bidder is responsible for obtaining all required permits.

- E. The bidder is responsible for contacting Call OKIE and appropriate utilities for detection of any sub-surface hazards.
- F. The bidder is responsible for clean up of the site after work has been completed.

LIMESTONE DRIVE
(PUBLIC STREET)

